

Roll Call Number

Agenda Item Number

60

DATE December 21, 2020

ORDERING CONSTRUCTION OF INGERSOLL AVENUE 42ND STREET TO POLK BOULEVARD RECONSTRUCTION AND FIXING A DATE FOR RECEIVING OF BIDS ON JANUARY 20, 2021 AND PUBLIC HEARING ON FEBRUARY 22, 2021 ENGINEER'S ESTIMATE IS \$3,620,000.00

WHEREAS, this Council deems it advisable and necessary to construct the below referenced improvement, all in accordance with the plans and specifications, and has caused to be prepared plans, specifications, and form of contract, together with estimate of cost, which are now on file in the City Engineer's Office, 2nd Floor, City Hall, 400 Robert D. Ray Drive, Des Moines, Iowa 50309, for public inspection for the construction of said improvements, and said plans, specifications and form of contract are deemed suitable for the making of said improvement, for which the State of Iowa Department of Transportation (IDOT) and the City of Des Moines, (CITY) have an agreement, previously approved by this Council, under which the IDOT has agreed to advertise, receive, open and tabulate sealed bids, and

WHEREAS, before said plans, specifications, form of contract, and estimated cost of the improvement may be approved, and contract for the construction of the improvement entered into, it is necessary to hold a public hearing.

BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF DES MOINES, IOWA: That the attached communication recommending construction of the following improvement and the method of financing; and also including the recommendation of the Des Moines City Engineer, as the Engineer, submitting plans, specifications, form of contract documents, and Engineer's estimate of cost for the construction of the following improvement:

Ingersoll Avenue 42nd Street to Polk Boulevard Reconstruction, 062019014 STBG-SWAP-1945(853)-SG-77

The improvement includes construction of Portland Cement Concrete (PCC) sidewalks, driveways, and Hot Mix Asphalt (HMA) paving, clearing and grubbing, earthwork, modified subbase, subdrains, erosion control, storm sewers, intakes, manholes, traffic control, traffic signals, permeable pavers, pavement markings, and surface restoration; all in accordance with the contract documents, including Plan File Nos. 620-174/272, on Ingersoll Avenue from Polk Boulevard to 42nd Street, Des Moines, Iowa

be and the same are hereby approved and accepted. The estimated construction cost for said improvement is \$3,620,000.00. The proposed plans, specifications, and form of contract documents are available for public inspection in the Des Moines City Engineer's Office.

BE IT FURTHER RESOLVED: That this Council hereby determines that it is necessary and advisable to construct said improvement in the manner set forth in the plans, specifications, and form of contract documents submitted by the Engineer; and that payment for the cost of said improvement shall be paid from the funding source identified below.

BE IT FURTHER RESOLVED: That a public hearing on said plans, specifications, form of contract documents, and Engineer's estimate of construction cost for said improvement be held in the MSC Board Room, 2nd Floor, Municipal Service Center, 1551 E. Martin Luther King Jr. Parkway, Des Moines, Iowa, at 5:00 p.m. on February 22, 2021, at which time this Council will consider any objections offered thereto or to the making of said improvement.

Roll Call Number

Agenda Item Number

bc

DATE December 21, 2020

BE IT FURTHER RESOLVED: That proposals will be received by the Iowa Department of Transportation, for the construction of said improvements, and the taking of bids in the manner required by law. Proposals received will be opened and tabulated by the Iowa Department of Transportation on January 20, 2021, after which the bids together with a report and recommendation of the Chief Civil Engineer, will be presented to City Council at its next meeting for action thereon.

BE IT FURTHER RESOLVED: That an appropriate Notice to Bidders for said improvement be posted, and Notice of Public Hearing for said improvement be published in the Des Moines Register, all as provided and directed by Chapter 26 and/or 314, Code of Iowa.

(City Council Comm	nunication Number <u>40.546</u> attached.)
Moved by	to adopt.
FORM APPROVED:	FUNDS AVAILABLE
s/Kathleen Vanderpool	
Kathleen Vanderpool Deputy City Attorney	Nickolas J. Schaul Director of Finance

Funding Source: 2020-2021 CIP, Page Street – 33, Roadway Reconstruction, ST260, Being: \$1,000,000 in Surface Transportation Block Program Federal-aid Swap Project funds being 80% eligible roadway construction costs under STBG-SWAP-1945(853)—SG-77 DOT SWAP, \$210,650 Storm Water Utility Funds, \$164,918.60 Des Moines Water Works, and the remaining \$2,244,431.40 in G.O. Bonds

COUNCIL ACTION	YEAS	NAYS	PASS	ABSENT
COWNIE				
WESTERGAARD				
GRAY				
BOESEN				
VOSS				
MANDELBAUM				
GATTO				
TOTAL				
MOTION CARRIED		l	I	I APPROVED

I, P. Kay Cmelik, City Clerk of said City Council, hereby certify that at a meeting of the City Council, held on the above date, among other proceedings the above was adopted.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my seal the day and year first above written.

Mayor	
11141	

CONSTRUCTION ESTIMATE

DEPARTMENT OF ENGINEERING CITY OF DES MOINES, IOWA

Activity ID 06-2019-014 STBG-SWAP-1945(853)—SG-77 DATE: 11/30/2020

PROJECT: INGERSOLL AVENUE RECONSTRUCTION POLK BOULEVARD TO 42ND ST

		T	·····		
0001			STIMATE		AMOUNT
	DESCRIPTION	UNIT	TOTAL	UNIT PRICE	TOTAL
่ถูกกว	CLEARING AND GRUBBING	UNIT	159.00	\$ 88.00	\$13,992,00
	EXCAVATION, CLASS 10, ROADWAY AND BORROW	CY	700.00	\$ 11.00	\$7,700.00
0003	EXCAVATION, CLASS 10, WASTE	CY	3600.00	\$ 22.00	\$79,200.00
0004	TOPSOIL, FURNISH AND SPREAD	CY	1000.00	\$ 22.00	\$22,000.00
0005	TOPSOIL, STRIP, SALVAGE AND SPREAD	CY	500.00	\$ 16,50	\$8,250.00
0006	COMPACTION WITH MOISTURE AND DENSITY CONTROL	CY	226,00	\$ 11.00	\$2,486.00
0007	SUBGRADE STABILIZATION MATERIAL, POLYMER GRID	SY	3000.00	\$ 4.40	\$13,200.00
8000	MODIFIED SUBBASE	CY	1847.00	\$ 88.00	\$162,536.00
0009	SHOULDER CONSTRUCTION, EARTH	STA	45.00	\$ 550.00	\$24,750.00
0010	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLA SS C,	SY	5060,00	\$ 77.00	\$389,620.00
0011	PORTLAND CEMENT CONCRETE PAVEMENT SAMPLES	LS	1.00	\$ 5,500.00	\$5,500.00
0012	HOT MIX ASPHALT STANDARD TRAFFIC, BASE COURSE, 3/4 IN. MIX	TON	1200.00	\$ 66,00	\$79,200.00
0013	HOT MIX ASPHALT STANDARD TRAFFIC, INTERMEDIATE COURSE, 1/2 I N. MIX	TON	605,00	\$ 66,00	\$39,930.00
0014	HOT MIX ASPHALT STANDARD TRAFFIC, SURFACE COURSE, 1/2 IN. MI X, NO SPECIAL FRICTION REQUIREMENT	TON	605.00	\$ 77.00	\$46,585.00
	ASPHALT BINDER, PG 58-28S, STANDARD TRAFFIC	TON	72.00	\$ 550,00	\$39,600.00
0016	ASPHALT BINDER, PG 58-28H, HIGH TRAFFIC	TON	73.00	\$ 550,00	\$40,150.00
	HOT MIX ASPHALT PAVEMENT SAMPLES	LS	1.00	\$ 5,500.00	\$5,500.00
	REMOVAL OF SIGN	EACH	27.00	\$ 220.00	\$5,940.00
	REMOVALS, AS RER PLAN	LS	1.00	\$ 5,500.00	\$5,500.00
	MODULAR BLOCK RETAINING WALL	SF	600.00	\$ 88,00	\$52,800.00
	MANHOLE, STORM SEWER, SW-401, 48 IN.	EACH	1.00	\$ 5,500,00	\$5,500.00
	MANHOLE, STORM SEVER, SW-401, 60 IN.	EACH	4.00	\$ 8,800.00	\$35,200.00
	MANHOLE, STORM SEWER, SW-401, 72 IN.	EACH	1.00	\$ 11,000.00	\$11,000.00
	MANHOLE, STORM SEWER, SW-402	EACH	1.00	\$ 11,000.00	\$11,000.00
		EACH	3.00	\$ 22,000.00	\$66,000.00
	MANHOLE, STORM SEWER, SW-403	EACH	2.00	\$ 4,400.00	\$8,800,00
	INTAKE, SW-501	EACH	2.00	\$ 6,600.00	\$13,200.00
	INTAKE, SW-505	EACH		\$ 8,800.00	\$26,400.00
	INTAKE, SW-506		3.00		\$118,800.00
	INTAKE, SW-509	EACH	12.00	\$ 9,900.00	
	INTAKE, SW-510	EACH	1.00	\$ 11,000.00	\$11,000.00
	MANHOLE ADJUSTMENT, MINOR	EACH	7,00	\$ 1,100.00	\$7,700.00
	CONNECTION TO EXISTING MANHOLE	EACH	1.00	\$ 1,650.00	\$1,650.00
	SUBDRAIN, LONGITUDINAL, (SHOULDER) 6 IN. DIA.	LF	2827.00	\$ 16.50	\$46,645.50
	SUBDRAIN, PERFORATED PLASTIC PIPE, 4 IN. DIA.	LF	380.00	\$ 11.00	\$4,180.00
	SUBDRAIN OUTLET, DR-303	EACH	26,00	\$ 440.00	\$11,440.00
	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 15 IN.	LF	316.00	\$ 88,00	\$27,808.00
	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 18 IN.	LF	213.00	\$ 99.00	\$21,087.00
	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 24 IN.	LF	517.00	\$ 110.00	\$56,870.00
	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 30 IN.	LF	75.00	\$ 148.50	\$11,137.50
0040	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 36 IN.	LF	319.00	\$ 187.00	\$59,653.00
0040 0041	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN.	LF	70,00	\$ 88,00	\$6,160.00
0040 0041					
0040 0041 0042	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN.	LF	70,00	\$ 88,00	\$6,160.00
0040 0041 0042 0043	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN.	LF LF	70.00 210.00	\$ 88.00 \$ 99.00	\$6,160.00 \$20,790.00
0040 0041 0042 0043 0044	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN.	LF LF LF	70,00 210,00 455,00	\$ 88,00 \$ 99.00 \$ 154.00	\$6,160.00 \$20,790.00 \$70,070.00
0040 0041 0042 0043 0044 0045	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN.	LF LF LF	70.00 210.00 455.00 50.00	\$ 88,00 \$ 99.00 \$ 154.00 \$ 198.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00
0040 0041 0042 0043 0044 0045	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN.	LF LF LF LF	70,00 210,00 455,00 50,00 34,00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00
0040 0041 0042 0043 0044 0045 0046	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN.	LF LF LF LF LF	70.00 210.00 455.00 50.00 34.00 1234.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 22.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$27,148.00
0040 0041 0042 0043 0044 0045 0046 0047	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN. STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL T O 36 IN. DIA.	LF LF LF LF LF LF	70.00 210.00 455.00 50.00 34.00 1234.00 351.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 22.00 \$ 55.00 \$ 55.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$27,148.00 \$19,305.00
0040 0041 0042 0043 0044 0045 0046 0047 0048	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN. STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA. ENGINEERING FABRIC	LF LF LF LF LF SY	70.00 210.00 455.00 50.00 34.00 1234.00 351.00 2336.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 22.00 \$ 55.00 \$ 55.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$27,148.00 \$19,305.00 \$12,848.00
0040 0041 0042 0043 0044 0045 0046 0047 0048 0049	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN. STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA. ENGINEERING FABRIC REMOVAL OF PAVEMENT	LF LF LF LF SY SY	70.00 210.00 455.00 50.00 34.00 1234.00 351.00 2336.00 13795.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 22.00 \$ 55.00 \$ 5.50 \$ 22.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$27,148.00 \$19,305.00 \$12,848.00 \$303,490.00
0040 0041 0042 0043 0044 0045 0046 0047 0048 0049 0050	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN. STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA. ENGINEERING FABRIC REMOVAL OF PAVEMENT REMOVAL OF INTAKES AND UTILITY ACCESSES	LF LF LF LF SY SY EACH	70.00 210.00 455.00 50.00 34.00 1234.00 351.00 2336.00 13795.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 22.00 \$ 55.00 \$ 5.50 \$ 22.00 \$ 1,100.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$27,148.00 \$19,305.00 \$12,848.00 \$303,490.00
0040 0041 0042 0043 0044 0045 0046 0047 0048 0049 0050 0051	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN. STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA. ENGINEERING FABRIC REMOVAL OF PAVEMENT REMOVAL OF INTAKES AND UTILITY ACCESSES REMOVAL OF SIDEWALK	LF LF LF LF SY SY EACH	70.00 210.00 455.00 50.00 34.00 1234.00 351.00 2336.00 13795.00 15.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 22.00 \$ 55.00 \$ 55.00 \$ 1,100.00 \$ 22.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$27,148.00 \$19,305.00 \$12,848.00 \$303,490.00 \$32,626.00
0040 0041 0042 0043 0044 0045 0046 0047 0048 0049 0050 0051 0052	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN. STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA. ENGINEERING FABRIC REMOVAL OF PAVEMENT REMOVAL OF INTAKES AND UTILITY ACCESSES REMOVAL OF SIDEWALK SIDEWALK, P.C. CONCRETE, 4 IN.	LF LF LF LF SY SY EACH SY	70.00 210.00 455.00 50.00 34.00 1234.00 351.00 2336.00 13795.00 15.00 1483.00 2120.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 55.00 \$ 55.00 \$ 22.00 \$ 22.00 \$ 55.50 \$ 55.50 \$ 55.50	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$27,148.00 \$19,305.00 \$12,848.00 \$303,490.00 \$32,626.00 \$116,600.00
0040 0041 0042 0043 0044 0045 0046 0047 0048 0049 0050 0051 0052 0053	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN. STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA. ENGINEERING FABRIC REMOVAL OF PAVEMENT REMOVAL OF INTAKES AND UTILITY ACCESSES REMOVAL OF SIDEWALK SIDEWALK, P.C. CONCRETE, 4 IN. SIDEWALK, P.C. CONCRETE, 6 IN.	LF LF LF LF SY SY EACH SY SY	70.00 210.00 455.00 50.00 34.00 1234.00 351.00 2336.00 15.00 1483.00 2120.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 22.00 \$ 55.00 \$ 5.50 \$ 22.00 \$ 1,100.00 \$ 22.00 \$ 55.00 \$ 60.50	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$27,148.00 \$19,305.00 \$12,848.00 \$303,490.00 \$16,500.00 \$116,600.00 \$11,616.00
0040 0041 0042 0043 0044 0045 0046 0047 0048 0050 0051 0052 0053 0054 0055	STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 15 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 18 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3000D (CLASS IV), 30 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 36 IN. STORM SEWER GRAVITY MAIN, TRENCHED, REINFORCED CONCRETE PIPE (RCP), 3750D (CLASS V), 42 IN. REMOVE STORM SEWER PIPE LESS THAN OR EQUAL TO 36 IN. STORM SEWER ABANDONMENT, FILL AND PLUG, LESS THAN OR EQUAL TO 36 IN. DIA. ENGINEERING FABRIC REMOVAL OF PAVEMENT REMOVAL OF INTAKES AND UTILITY ACCESSES REMOVAL OF SIDEWALK SIDEWALK, P.C. CONCRETE, 4 IN. SIDEWALK, P.C. CONCRETE, 6 IN. DETECTABLE WARNINGS	LF LF LF LF SY SY EACH SY SY SY	70.00 210.00 455.00 50.00 34.00 1234.00 351.00 2336.00 15.00 1483.00 2120.00 192.00	\$ 88.00 \$ 99.00 \$ 154.00 \$ 198.00 \$ 220.00 \$ 55.00 \$ 55.00 \$ 22.00 \$ 55.50 \$ 22.00 \$ 1,100.00 \$ 22.00 \$ 65.00 \$ 66.00	\$6,160.00 \$20,790.00 \$70,070.00 \$9,900.00 \$7,480.00 \$19,305.00 \$12,848.00 \$303,490.00 \$16,500.00 \$116,600.00 \$11,616.00

		Т.	STIMATE	DUNITO	AMOUNT
NO.	DESCRIPTION		T	UNIT PRICE	TOTAL
0058	REMOVAL OF PAVED DRIVEWAY	UNIT	828.00	\$ 22.00	\$18,216,00
0059	REMOVAL AND REINSTALLATION OF FENCE, CHAIN LINK	LF	20,00	\$ 110.00	\$2,200.00
0060	REMOVE AND REINSTALL SIGN AS PER PLAN	EACH	28.00	\$ 440.00	\$12,320.00
0061	PERFORATED SQUARE STEEL TUBE POSTS	LF	50.00	\$ 27.50	\$1,375.00
0062	** ** *** *** *** *** *** *** *** ***	SF	51.00	\$ 44.00	\$2,244.00
0063	TYPE A SIGNS, SHEET ALUMINUM TRAFFIC SIGNALIZATION	LS			
}		LS	1,00		\$5,500.00
 	CONSTRUCTION SURVEY	+	1.00	\$ 16,500.00	\$16,500.00
0065	PAINTED PAVEMENT MARKINGS, DURABLE	STA	94.25	\$ 176.00	\$16,588.00
0,066	PERMANENT TAPE MARKINGS, PROFILED PAVEMENT MARKING TAPE	STA	35.33	\$ 220.00	\$7,772.60
0067	PAINTED SYMBOLS AND LEGENDS, DURABLE	EACH	26.00	\$ 385.00	\$10,010.00
0068	GROOVES CUT FOR PAVEMENT MARKINGS	STA	129.58	\$ 55.00	\$7,126.90
0069	GROOVES CUT FOR SYMBOLS AND LEGENDS	EACH	26,00	\$ 220.00	\$5,720.00
0070	SAFETY CLOSURE ,	EACH	26,00	\$ 330,00	\$8,580.00
0071	TRAFFIC CONTROL	LS	1.00	\$ 22,000.00	\$22,000.00
-	PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	CDAY	14.00	\$ 220.00	\$3,080.00
	MOBILIZATION	LS	1.00	\$167,772.90	\$167,772.90
0074	TRENCH FOUNDATION	TON	200.00	\$ 71.50	\$14,300.00
0075	REPLACEMENT OF UNSUITABLE BACKFILL MATERIAL	CY	200.00	\$ 88.00	\$17,600.00
0076	WATER MAIN, TRENCHED, DUCTILE IRON PIPE (DIP), 8 IN.	LF	120.00	\$ 110.00	\$13,200.00
0077	WATER MAIN, TRENCHED, DUCTILE IRON PIPE (DIP), 12 IN.	LF	340.00	\$ 137.50	\$46,750.00
0078	FITTINGS BY WEIGHT, DUCTILE IRON	LB	5156,00	\$ 9.35	\$48,208.60
0079	WATER SERVICE STUB, COPPER, 1 IN.	LF	200.00	\$ 27.50	\$5,500.00
0080	WATER SERVICE CURB STOP AND BOX, COPPER, 1 IN.	EACH	10,00	\$ 2,200.00	\$22,000.00
0081	DELIVER AND STOCKPILE SALVAGED MATERIALS	LS	1.00	\$ 5,500.00	\$5,500.00
0082	('EACH' ITEM) GRATE INTAKE - DROP IN INTAKE PROTECTION	EACH	7.00	\$ 330,00	\$2,310.00
0083	('EACH' ITEM) MAGNESIUM ANODE, 32-POUND	EACH	11,00	\$ 1,760.00	\$19,360.00
0084	('EACH' ITEM) REMOVAL OF EXISTING AND INSTALLATION OF NEW FIRE HYDRANT ASSEMBLY, WM-201	EACH	1.00	\$ 7,150.00	\$7,150.00
0085	('EACH' ITEM) SUBDRAIN CLEANOUT	EACH	5,00	\$ 660.00	\$3,300.00
0086	('EACH' ITEM) VALVE BOX ADJUSTMENT	EACH	11.00	\$ 220.00	\$2,420.00
0087	('EACH' ITEM) WATER SERVICE TRANSFER, 1 IN.	EACH	2.00	\$ 4,400.00	\$8,800.00
0088	('LINEAR FEET' ITEM) REMOVAL OF TROLLEY TRACKS	LF	2000,00	\$ 49.50	\$99,000.00
0089	('LUMP SUM' ITEM) CONCRETE WASHOUT	LS	1.00	\$ 5,500.00	\$5,500.00
0090	('LUMP SUM' ITEM) MAINTENANCE OF SOLID WASTE COLLECTION	LS	1.00	\$ 5,500.00	\$5,500.00
0091	('SQUARE FEET' ITEM) LIMESTONE RETAINING WALL	SF	270.00	\$ 88.00	\$23,760.00
0092	('SQUARE FEET' ITEM) TYPE A CONCRETE STEPS WITH HANDRAIL	SF	60.00	\$ 220.00	\$13,200.00
0093	('SQUARE FEET' ITEM) TYPE B CONCRETE STEPS WITH HANDRAIL	SF	60,00	\$ 330.00	\$19,800.00
0094	('SQUARE YARDS' ITEM) CEMENT TREATED SUBGRADE	SY	11080.00	\$ 16.50	\$182,820.00
	('SQUARE YARDS' ITEM) PERMEABLE PAVERS	SY	933.00	\$ 110.00	\$102,630.00
0096	('TONS' ITEM) FILTER AGGREGATE	TON	155.00	\$ 66.00	\$10,230.00
0097	('TONS' ITEM) STORAGE AGGREGATE	TON	820.00	\$ 66.00	\$54,120.00
	('TONS' ITEM) TEMPORARY SURFACING, RAP MILLINGS	TON	1000.00	\$ 55.00	\$55,000.00
	MULCHING	ACRE	4.00	\$ 2,750.00	\$11,000.00
	HYDRAULIC SEEDING	ACRE	4.00	\$ 5,500.00	\$22,000.00
	STABILIZING CROP - SEEDING AND FERTILIZING (URBAN)	ACRE	4.00	\$ 2,750.00	\$11,000.00
	TURF REINFORCEMENT MAT, TYPE 4	SQ	19.00	\$ 165.00	\$3,135.00
	SILT FENCE	LF	2000,00	\$ 3.30	\$6,600.00
	REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	LF	2000.00	\$ 0.55	\$1,100.00
	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	LF	500,00		
	STABILIZED CONSTRUCTION ENTRANCE, EC-303	LF	100.00	\$ 0.28 \$ 165.00	\$140.00
	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN, DIA.	LF			\$16,500.00
			6300.00	\$ 4.40	\$27,720.00
	REMOVAL OF PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE	LF	6300.00	\$ 0,55	\$3,465.00
	OPEN-THROAT CURB INTAKE SEDIMENT FILTER, EC-602	LF	104,00	\$ 27.50	\$2,860.00
	MAINTENANCE OF OPEN-THROAT CURB INTAKE SEDIMENT FILTER	EACH	13.00	\$ 110.00	\$1,430.00
	REMOVAL OF OPEN-THROAT CURB INTAKE SEDIMENT FILTER	EACH	13.00	\$ 55.00	\$715.00
	MOBILIZATIONS, EROSION CONTROL	EACH EACH	10.00	\$ 550.00 \$ 1,100.00	\$5,500.00 \$11,000.00
0113	MOBILIZATIONS, EMERGENCY EROSION CONTROL				

Prepared By: Christopher Kuhl	
Checked By:	

TOTAL CONSTRUCTION COST \$3,620,000.00